GRAYCO
CONSTRUCTION SERVICES

WHAT TO EXPECT · INSURANCE CLAIMS

# Your insurance claim timeline

Who does what — from the day damage happens to your final walkthrough. Every claim is different; your PM will tell you where you are at each step.

| STEP | YOU | GRAYCO | YOUR INSURANCE COMPANY |
|---|---|---|---|
| DAY 1<br>**Protect the property** | Keep everyone safe. Call us for emergency help. | Board-up, tarping or water extraction to stop further damage (24/7). | — |
| DAY 1–2<br>**Report the claim** | Report the loss; get a claim number. Keep receipts for emergency costs. | Help you gather photos and details for the report. | Opens the claim; assigns an adjuster. |
| FIRST DAYS<br>**Inspect & document** | Share your claim #, adjuster contact and policy paperwork. | Photograph and document all damage; prepare our own independent estimate. | — |
| BEFORE WORK<br>**Authorize the work** | Sign the Work Authorization. You may cancel within 3 business days. | Explain the form and what GrayCo will do on your behalf. | — |
| PER INSURER<br>**Adjuster inspection** | Be available if possible. | Meet the adjuster on site with our photos, measurements and estimate. | Inspects and writes the scope of loss. |
| AFTER INSPECTION<br>**Approved scope** | Review the scope with us. Pay your deductible as your policy requires. | Walk you through the scope line by line; schedule the work. | Issues payment, less the deductible and any held-back depreciation. |
| WATER / FIRE<br>**Mitigation & drying** | Allow access for daily monitoring. | Water: extraction, drying with daily moisture readings. Fire: smoke/soot removal, odor treatment, demo. | — |
| PER SCOPE<br>**Rebuild & supplements** | Approve any work outside the insurance scope in writing. | Restore to pre-loss condition. Hidden damage is photographed and submitted as a supplement. | Reviews and approves supplements. |
| END OF JOB<br>**Completion & sign-off** | Walk the finished work; sign the Certificate of Completion & Satisfaction. | Final walkthrough, punch list, final clean-up. | Receives completion documents. |
| CLOSEOUT<br>**Final funds & warranty** | Keep your closeout documents. | Issue your written warranty and final lien waiver after final payment. | Releases final / recoverable depreciation. |

### Typical durations

- **Water:** emergency mitigation 1–3 days; structural drying 3–5 days (monitored daily until dry standards are met); rebuild per approved scope.
- **Fire:** board-up Day 1; mitigation weeks 1–2; engineer review if needed weeks 2–3; then rebuild.
- Supplements for hidden damage can extend the timeline.

### Honest about your deductible

**We never ask you to inflate or skip your deductible** — and we never offer to "cover" it. Your out-of-pocket cost is limited to your deductible unless you approve extra work in writing.

### Paperwork you'll see

- Work Authorization (3-day right to cancel)
- Our estimate & the insurer's scope
- Supplements, with photos
- Change Orders for out-of-scope work
- Certificate of Completion & Satisfaction
- Warranty certificate & lien waiver

Your insurance company decides what your policy covers. GrayCo documents the damage, communicates with your adjuster and keeps you informed — you will receive copies of what we submit.

(901) 585-0944 office@grayco-cs.com grayco-cs.com

GrayCo Construction Services, LLC · 4007 Broadway Rd, Bartlett, TN 38135
TN License #85034 BCB · AR License #0486990627 · MS License #27769